

# National Institute of Ayurveda

Deemed to be University (de-novo)

(Ministry of AYUSH, Govt. of India)

## Short Inviting Quotation

File No. Estate/ Simulation Lab/2025/ 2508

Date: 26-05-2025

Joint Director (Administration) Jaipur Invited Short Notice Inviting Quotation on behalf of Vice Chancellor, NIA, Jaipur Sealed Covered Envelope % Rate (Above or Below) Tender /Quotation from experience agency for the following work :-

**Name of Work:** Providing & Fixing Glass Film & Finishing Work in Simulation Lab.

Date & Time Issuing Tender:

Up to 26-05-2025, 03:00 PM

Date & Time Receipt of Tender:

Up to 02-06-2025, 03:00 PM

Date & Time Opening Tender:.

Up to 03-06-2025, 03:30 PM

Sr. No.	Description of Work	Estimate Cost	Time Allowed
1.	Providing & Fixing Glass Film & Finishing Work in Simulation Lab	2,06,284/-	15 Days

### ➤ Conditions :-

- The Contractor Should be registered in State Govt./Central Govt./PSU etc. and must produce along with the application the attached copy of registration
- Work shall be carried out as per CPWD Specification.
- All Materials and human recourses required shall be arranged by the firm
- The rate quoted by agency shall be inclusive of all taxes, GST and nothing extra shall be paid on quoted rates on any account.
- Work order may be terminated at any stage, if performance is not found satisfactory.
- The time allowed is 45 days for complete from the date of issue work order
- Tender/Quotation uploaded on institute website ([www.nia.nic.in](http://www.nia.nic.in))
- Payment should be made after bill produced by the agency.


Cont... Page 2

**Detailed Estimate****Name of Work : P&F Glass Film & Finishing Work in Simulation Lab NIA, Jaipur**

S. No.	Work Description	Qty	Unit	Rate	Amt in Rs.
1	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	250	sqm	156.05	39012.5
2	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	250	sqm	25.15	6287.5
3	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
3.1	Two coats	250.00	sqm	142.80	35700.00
4	Filling the gap in between aluminium/ stone/ wood frame and adjacent RCC/Brick/ Stone/ wood/ Ceramic/ Gypsum work by providing weather/ structural non sag elastomeric PU sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete, complying to ASTM C920, DIN 18540-F & ISO 11600				
4.1	Upto 10 mm depth and 10 mm width	173.00	metre	200.95	34764.35
5	P&F Film on Toughened Glass at Simulation lab as per direction of Estate In-charge.	1460.00	Sq. Feet	62	90520
(A) Total Rs.					2,06,284.35
Say					2,06,284.00

**Note : Percentage % Above/Below Should Be Quote**

  
Estate In-Charge


  
Joint Director (Admin.)  
संयुक्त निदेशक (प्रशासनिक)  
राष्ट्रीय आयुर्वेद संस्थान, जयपुर  
Joint Director (Admin.)  
National Institute Ayurveda, Jaipur