



राष्ट्रीय आयुर्वेद संस्थान  
मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64)/सम्पदा/2022/ 6982

दिनांक : 28.07.2022

अल्पकालीन निविदा

2-8-22

संस्थान शरीर क्रिया विभाग कक्ष संख्या 236 में Brick Wall Partiation का कार्य कर कक्ष को 02 भागों में विभाजित करने का कार्य करवाया जाना है। जो निम्नलिखित विवरण अनुसार निविदाओं के माध्यम से कार्य करवाया जाना है इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 04.08.2022 को सांय 4:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करें। कार्य का विवरण निम्नप्रकार है :-

Sr. No.	Discription of Work	Qty.	Rate per unit	Total Amount
<b>Civil Work</b>				
1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	03 Cum		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	04 Each		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :	06 Cum		
4	15 mm cement plaster on rough side of single or half brick wall of mix:	40 Sqm		
5	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	125. Sqm		
6	Providing and applying white cement based putty of average thickness 1 mm. of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	170.00 Sq. mtr.		
7	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ liter of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and color.	170.00 Sq.mtr.		
8	Providing Pine wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position.	02 Nos.		
<b>Electrical Work</b>				
9.	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable in surface / recessed steel conduit, with piano type switch, phenolic laminated sheet, suitable size MS box and earthing the point with 1.5 sq.mm FRLS PVC insulated copper conductor single core cable etc. as required.	10 Nos.		
10.	Wiring for light/ power plug with 4X4 sq. mm FRLS PVC insulated copper conductor single core cable in surface/ recessed steel conduit alongwith 2 Nos. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	60 mtr.		
GST				

1. उक्त कार्य का भुगतान सन्तोषप्रद होने पर किया जायेगा।
2. उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन में GST का उल्लेख करना अनिवार्य है अन्यथा प्राप्त कोटेशन में प्रस्तुत दर को GST सहित माना जावेगा।
4. कार्य आवार्ड होने के पश्चात एल-1 फर्म को 05 दिवस के भीतर कार्य प्रारम्भ करना होगा।
5. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

Prashanshik Adhikari