

**राष्ट्रीय आयुर्वेद संस्थान**  
**मानद विश्वविद्यालय (डी-नोवो), जयपुर**

क्रमांक एफ. 4(64)/सम्पदा/2023/10452

दिनांक : 06.09.23

**अल्पकालीन निविदा**

संस्थान रसायनशाला में पाउडर फिलिंग मशीन स्थापित गई है जिस हेतु उक्त मशीन के कम्प्रेसर को स्थापित करने हेतु प्लेटफॉर्म बनवाया जाना है, एवं कम्प्रेसर की सुरक्षा हेतु उसको लौहे की जाली से कवर कर उपर की तरफ फाईबर शीट से कवर करने का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है, इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 12.09.2023 को मध्यांन 3:00 बजे तक सीलबन्ध लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करें। कार्य का विवरण निम्नप्रकार है :-

S.N	Description of Work	Qty.	Rate per unit	Amount
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	1.50 cum		
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	1.50 cum		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	2 cum		
4	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	2 cum		
5	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	1.50 cum		
6	Fixing of hard drawn steel wire fabric 75x25 mm mesh of wight not less than 7.75 kg/Sqm to M.S. frame & priming coat with approved steel primer, welding etc. all complete. (The wire fabric will be supplied from the institute free of cost, as and where basis, the Contractor has to make the wire fabric suitable by cutting etc as per site requirement)	30 Sqm		
7	CEMENT PLASTER (IN FINE SAND) 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	7 Sqm		
8	Fixing of Equal M.S. Angle 25x25x5 of wight not less than 1.8 kg/mtr to M.S. frame & priming coat with approved steel primer, welding etc. all complete. (The M.S. angle will be supplied from the institute free of cost, as and where basis, the Contractor has to make the ms angle suitable by cutting etc as per site requirement)	75 Kg		
9	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick flat	30 Sqm		
10	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	40 Sqm		
<b>Total Rupees</b>				
<b>GST</b>				

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

Sd/  
उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

01. प्रतिष्ठापन शाखा को दी जाकर लेख है दिनांक 12.09.2023 को मध्यांन 3:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावे।

6/9  
उप निदेशक (प्रशासन)