

राष्ट्रीय आयुर्वेद संस्थान
मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64)/सम्पदा/2023/76२०

दिनांक : 26-7-23

अल्पकालीन निविदा

संस्थान में नव निर्मित गेस्ट हाउस, कैंटीन ब्लॉक एवं संस्थान की इत्यादि भवनों की छतों पर रखे VRV Type AC के आउटडोर यूनिट्स की सुरक्षा हेतु उनके चौरों और लौहे का जाल बनाकर उसको पुरी तरह से फाईबर शीट से कवर करवाये जाने का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है, इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 02.08.2023 को मध्यांन 3:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करे। कार्य का विवरण निम्नप्रकार है :-

S.N	Description of Work	Qty.	Rate per unit	Amount
1.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete			
	Electric resistance or induction butt welded tubes	800 kg		
2.	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.			
	2 mm thick flat	75 Sq. Mtr		
3.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :			
	Two or more coats on new work	150 Sq. Mtr		
4.	Fixing of hard drawn steel wire fabric 75x25 mm mesh of wight not less than 7.75 kg/Sqm to M.S. frame & priming coat with approved steel primer, welding etc. all complete. (The wire fabric will be supplied from the institute free of cost, as and where basis, the Contractor has to make the wire fabric suitable by cutting etc as per site requirement)	150 Sq. Mtr		
	Total Rupees			
	GST			

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

01. प्रतिष्ठापन शाखा को दी जाकर लेख है दिनांक 02.08.2023 को मध्यांन 03:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।

उप निदेशक (प्रशासन)