

राष्ट्रीय आयुर्वेद संस्थान
मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64)/सम्पदा/2024/22326

दिनांक : 23.8.24

अल्पकालीन निविदा

संस्थान अगदतंत्र विभाग के म्यूजियम कक्ष/प्रेक्टिल कक्ष में सिविल से संबंधित विभिन्न प्रकार का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है, इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 29.02.2024 को मध्याह्न 3:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करें। कार्य का विवरण निम्नप्रकार है :-

S.N.	Work Description	Qty.	Rate per unit	Amount
1	Providing and laying gang saw cut 30 mm thick, mirror polished pre moulded and pre polished machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge.			
	With granite stone of colour black, cherry/ruby red of area less than 0.50 sqm.	3.50 Sqm	sqm	
2	Providing and fixing white vitreous china laboratory sink with C.I. brackets, C.P. brass chain with rubber plug, 40 mm C.P. brass waste and 40mm C.P. brass trap with necessary C.P. brass unions complete, including painting of fittings and brackets, cutting and making good the wall wherever required :			
	Size 600x450x200 mm	1.00 Each	each	
3	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with :			
	4.0 mm thick glass panes	0.50 Sqm	sqm	
4	Providing and laying gang saw cut 18 mm thick, mirror polished pre moulded and pre polished machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge.			
	With granite stone of area less than 0.50 sqm.	0.75 Sqm	sqm	
5	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.			
	Cement mortar 1:4 (1 cement : 4 coarse sand)	0.80 Sqm	sqm	
6	12 mm cement plaster of mix :			
	1:6 (1 cement : 6 coarse sand)	10 Sqm	sqm	
7	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	5 Sqm	sqm	
8	Providing and fixing horizontal stone 40 mm thick and upto 80 cm projection in cement mortar 1:4 (1 cement : 4 coarse sand), including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade :			
	Red sand stone	5 Sqm	sqm	
9	Providing and fixing bright finished brass handles with screws etc. complete:			
	125 mm	24 Each	each	
10	Providing and fixing ISI marked oxidised M.S. door latches conforming to IS:5930 with screws etc. complete :			
	250x20x6 mm	1 Each	each	
11	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :			
	150 mm diameter	1 Meter	metre	
12	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. :			
	With float glass panes of 4.0 mm thickness (weight not less than 10kg/sqm)	0.5 Sqm	sqm	
13	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore	1 Each	each	
14	Cutting holes up to 30x30 cm in walls including making good the same:			
	With common burnt clay F.P.S. (non modular) bricks	2 Each	each	
15	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.			
	For thickness of tiles 10 mm to 25 mm	0.50 Sqm	sqm	


16	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	0.20 Cum		
17	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall : 20 mm dia nominal bore	15 meter		
	Total Rupees			
	GST			

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।


 उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

प्रतिष्ठापन शाखा (रिसिप्ट) को दी जाकर लेख है दिनांक 29.02.2024 को मध्याह्न 03:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।


 उप निदेशक (प्रशासन)