

# राष्ट्रीय आयुर्वेद संस्थान

## मानद विश्वविद्यालय (डी-नोवो)

### अल्पकालीन निविदा

संस्थान सैन्ट्रल लैब के बाहर जाँच करवाने हेतु आने वाले मरीजों की सुविधा के लिए प्रतिकालय शेड बनाने का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवया जाना है इच्छुक फर्म कार्य करने हेतु साईट का निरीक्षण कर अपनी निविदाएं दिनांक 05.07.2024 को मध्यांन 3:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करें। कार्य का विवरण निम्नप्रकार से है:-

Sr. No.	Work Description	Qty.	Rate Per Unit	Amount
1.	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	0.50 Cum		
2	Providing and fixing in position factory made non asbestos fibre reinforced aerated cement sandwich wall/roof/floor light weight solid core panels made of light weight cement concrete core composed of OPC cement, pulverized flyash, quick lime, cotton pulp & Gypsum in mortar state mixed with aeration agent in a preset mould. The outer face on both sides of the panels will be non asbestos fibre cement board confirming to IS :14862:2000. These solid wall panels are installed using Galvanized iron steel tracks/C channel of 1 mm thick of required sizes as recommended by manufacturer's and fixed to floor and RCC soffit in plumb to each other with steel screw/fasteners. The panel shall be fixed vertically with tongue & groove joint with cement based polymer modified jointing compound. The exposed surface finished with fibre mesh/glass fibre tape with polymer based jointing compound having superior flexibility. Panels should be used as floor & roofing with additional structural support, steel or RCC depending upon the design. All the operation shall be completed in all respect as per drawings, Manufacturers specifications and under the overall direction of Engineer-in-Charge (Cost of all the material is included except "tracks/C channel" which will be paid separately). Non load bearing panels 75 mm thick of required size (minimum 5 mm thick fibre cement board Type A, Category IV as per IS: 14862:2000 on both faces)	35.00 Cum		
3	Providing and fixing Stainless Steel light weight spikes 110 mm height adjoined over the strong polycarbonate base/ strip, spikes over the length with screws, silicon glue/ wire ties, washers, etc. UV resistant angled for the protection and discourageing unwanted birds and animals, with suitable ledge width protection upto 100mm including all accessories complete as per engineer in charge.	25.00 Sqm		
4	Providing & Applying weather proof sealant on outer joints of approved make confirming to IS & directed by Engineer-in-charge. Sealant 25 mm x10 mm at joints.	10.00 Mtr		
5	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of	300.00 Kg.		

	approved steel primer all complete.			
6	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes.	300.00 Kg.		
7	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	5.00 Kg		
8	Providing and fixing bolts including nuts and washers complete.	5.00 Kg		
9	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	250.00 Kg		
10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)	2.00 Cum		
	Total			
	GST			

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशनके साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

01. प्रतिष्ठापन शाखा (रिसिप्ट) को दी जाकर लेख है दिनांक 05.07.2024 को मध्यांन 03:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।

उप निदेशक (प्रशासन)