

**राष्ट्रीय आयुर्वेद संस्थान
मानद विश्वविद्यालय (डी-नोवो)**

अल्पकालीन निविदा

संस्थान योगा यूनिट के बाहरी तरफ की दिवार काफी जर्जर हो चुकी है जिसे रिपेयर एवं दिवारों पर उगे हुए पेड पौधों को हटवाये जाने व छज्जों की रिपेयरिंग कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है। इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 22.07.2024 को मध्यांन 3:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महादेय को प्रेषित करें। कार्य का विवरण निम्नप्रकार से है:-

S.N.	Work Description	Qty.	Rate Per Unit	Amount
1.	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meters lead as per direction of Engineer-in-charge : In lime mortar	45 Cum		
2.	Dismantling C.I. or asbestos rain water pipe with fittings and clamps including stacking the material within 50 meters lead : 100 mm dia pipe	30 Mtr		
3.	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. Beyond 30 cm girth up to and including 60 cm girth each	02 Each		
4.	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	15 sqm		
5.	Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, up to 25 meter height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40 mm dia M.S. tube, placed 1.5 meter center to center, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. Note:- (1) The elevational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works.	130 Sqm		
6.	Repair to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sqm and under, including cutting the patch in proper shape, raking out joints and preparing plastering the wall surface with white cement based polymer modified self curing mortar, including disposal of rubbish, all complete as per the direction of Engineer-In-Charge.	30 Sqm		
	Total			
	GST			

- फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
- फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
- फर्म द्वारा कोटेशनके साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
- कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

संयुक्त निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

01. प्रतिष्ठापन शाखा (रिसिप्ट) को दी जाकर लेख है दिनांक 22.07.2024 को मध्यांन 3:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।

संयुक्त निदेशक (प्रशासन)