

राष्ट्रीय आयुर्वेद संस्थान
मानद विश्वविद्यालय (डी-नोवो), जयपुर

क्रमांक एफ. 4(64)/सम्पदा/2023/ 8916

दिनांक : 17/8/23

अल्पकालीन निविदा

संस्थान अग्निवेश/नागार्जुन/स्वामी लक्ष्मीराम/अमृता छात्रावासों की छत पर आर.ओ. रखने हेतु बने लौहे के जाल को फाईबर शीट/प्रोफाईल शीट कवर करने का कार्य एवं वैदेही छात्रा-छात्रावास की छत पर आर.ओ. हेतु लौहे का नया जाल बनाकर उसको फाईबर शीट/प्रोफाईल शीट से कवर करवाने का कार्य निम्नलिखित विवरण अनुसार अल्पकालीन निविदाओं के माध्यम से करवाया जाना है, इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 23.08.2023 को मध्यांन 3:00 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करे। कार्य का विवरण निम्नप्रकार है :-

S.N	Description of Work	Qty.	Rate per unit	Amount
1.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	215 kg		
2.	Fixing of hard drawn steel wire fabric 75x25 mm mesh of wight not less than 7.75 kg/Sqm to M.S. frame & priming coat with approved steel primer, welding etc. all complete. (The wire fabric will be supplied from the institute free of cost, as and where basis, the Contractor has to make the wire fabric suitable by cutting etc as per site requirement)	30 Sqm		
3.	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified.			
	2 mm thick flat	130 sqm		
4.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work			
		155 Sqm		
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)			
		3.20 Sqm		
6.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)			
		1.65 Sqm		
7.	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.			
		12 Sqm		
Total Rupees				
GST				

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. फर्म को उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

SL
उप निदेशक (प्रशासन)

प्रतिलिपि:- सूचनार्थ हेतु प्रेषित।

01. प्रतिष्ठापन शाखा को दी जाकर लेख है दिनांक 23.08.2023 को मध्यांन 03:00 बजे तक उक्त कार्य की निविदा प्राप्त कर सम्पदा विभाग में भिजवाये जाने की व्यवस्था करावें।

h
उप निदेशक (प्रशासन)