

राष्ट्रीय आयुर्वेद संस्थान, जयपुर  
मानद विश्वविद्यालय

क्रमांक एफ. 5(74)/सम्पदा/2023/ 1842


दिनांक : 16-06-23

अल्पकालीन निविदा

संस्थान ऑडिटोरियम में फायर फाईटिंग सिस्टम को एडवांस करने हेतु उसमें प्रेशर पम्प, स्टार्टर पैनल, मोटर आदि सामान लगाने का कार्य निम्नलिखित विवरण अनुसार निविदाओं के माध्यम से करवाया जाना है इच्छुक फर्म साईट का निरीक्षण कर अपनी निविदाएं दिनांक 22.06.2023 को मध्याह्न 2:30 बजे तक सीलबन्द लिफाफे पर उक्त निविदा का नाम लिखकर संस्थान में कुलपति महोदय को प्रेषित करें। कार्य का विवरण निम्नप्रकार है :-

S. N	Description	Qty.	Rate per unit	Amount
1	(A) Supplying, Installtion, Testing & Commissioning of Electric Driven Main Fire Pump Suitable for automatic operation and consisting of following, complete in all respects, as required : (B) Horizontal type, multistage, Centrifugal, split casing pump of cast iron body & bronze impeller with stainless steel shaft, mechanical seal conforming to IS 1520. (C) Suitable HP Squirrel cage induction motor, TEFC, synchronous speed 1500 RPM, suitable for operation on 415 volts, 3 phase 50 HZ, AC Supply with IP 55 protection for enclosure, horizontal foot mounted type with Class-'F' insulation, conforming to IS-325. (D) M.S. fabricated common base plate, coupling, coupling gurad, foundation bolts etc. as required. (E) Suitable cement concrete foundation duly plastered with anti vibration pads. <b>2850 lpm at 35 m Head</b>	01 nos.		
2	Designing, Suuply, Installtion, Testing and commissioning of system controller to control operation of main electric fire pump, diesel pump, Pressurization pump, Terrace pump in sequence as per specification consisting of relays, timers. Sensors annunciation window for fault indication, complete as per specification.	01 nos.		
3	Providing, laying, testing & Commissioning of 'C' Class heavy duty MS Pipe conforming to IS 3589/IS1239 including welding, fettings like elbow, Tees, flanges, tapers, nuts bolts, gaskets etc and fixing the pipe on the surface/wall with suitable clamp/supports frame and painting with two or more coats of synthetic enamel paint of required shade complete as required. <b>100 mm dia</b>	10 mtr.		
4	Providing, installtion, testing & Commissioning of non-return valve of following sizes conforming to IS: 5312 complete with rubber gasket, G.I. bolts, nuts, washers etc. as required <b>100 mm dia</b>	01 nos.		
5	Supplying fixing, Testing & Commissioning of butterfly valve of PN 1.6 rating with bronze/gunmatel seat duly ISI marked complete with rubber gasket, G.I. bolts, nuts, washers etc. gaskets conforming to IS: 13095 of following size required. <b>100 mm dia</b>	02 nos.		
6	Supplying fixing, Testing & Commissioning of pressure gauze and pressure switch.	02 nos.		
7	Supplying, Installtion, Testing of 10 Sqm 3 core armoured cable	180 mtr.		
8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes and fittings for water storage tank to existing water supply line.	01 Job		
9.	Foundation for 5000 liter (02 nos.) water tank as per 1:4:8 (1 Cement : 4 coarse sand )	01 Job.		
	<b>Total Rupees</b>			
	<b>GST</b>			

1. फर्म को कार्य का भुगतान कार्य सन्तोषप्रद होने पर किया जायेगा।
2. उपरोक्त विवरणानुसार ही कोटेशन भर कर प्रस्तुत करना होगा।
3. फर्म द्वारा कोटेशन के साथ GST का प्रमाण पत्र संलग्न करना अनिवार्य है।
4. कार्य पूर्ण होने पर बिल 02 प्रतियों में सम्पदा विभाग में प्रस्तुत करना होगा जिससे भुगतान की कार्यवाही की जा सके।

  
उप निदेशक (प्रशासन)